

## Christians Have



<b>Location</b>	Solrød Strand	<b>Year of completion</b>	2015 – 2018
<b>Number of homes</b>	164	<b>Type of home</b>	Elderly homes
<b>System solution</b>	AWCS	<b>Number of fractions</b>	1
<b>Fraction</b>	Residual	<b>Number of wastemagaziens</b>	13 stk.
<b>Tank type</b>	Ground	<b>Number of inlets</b>	13 pcs.
<b>Pipe dimension</b>	Ø315	<b>Pipe material</b>	PE100 Safetech PN 6.3
<b>Pipe length Approx.</b>	740 m.	<b>Number of containers</b>	1pcs. 20-foot container

### Description of the project

Aerbin has supplied a automatic waste collection system and 3 bio chutes. There are also 5 chutes for residual waste. The magazines are connected with Ø315 pipes to a small mini central outside the building. The piperoute is run underground from the magazines inside the building to the central.