

Sølund



Location	Nørrebro	Year of completion	2020 – 2028
Number of homes	383	Type of home	Nursing homes
System solution	AWCS	Number of fractions	1
Fraction	Residual	Number of wastemagazines	4 pcs.
Tank type	Internal magazine	Number of chutes inlets	18 pcs.
Pipe dimension	Ø315mm	Pipe material	PE100 Safetech PN 6.3
Pipe length Approx.	270 m.	Number of containers	1pcs. x 20 ft container

Description of the project

With the construction of Sølund of the Future, the City of Copenhagen, Samvirkende Boligselskaber and KAB want to set new high standards for care homes, children's institutions, youth housing and senior cohousing communities. But we want more than that. We want to fulfil our ambition to create buildings that can serve as a framework for intergenerational communities in the city.